



**PERMIT TO CONSTRUCT
Onsite Wastewater System**

File Nbr **2020070005**
County: Saluda

Name: JEFF RIKARD

Type Facility: HOUSE

Subdivision: PALMETTO POINTE

Block: Lot: 42

Address: 3079 WINDMILL RD
LEESVILLE, SC 29070

Site: LONGVIEW DR LOT 42
LEESVILLE, SC

Program Code: 360

System Code: 815

TM No.:

Water Supply: PUBLIC

PERMIT TO CONSTRUCT SYSTEM SPECIFICATIONS

Daily Flow (gpd): 360

Tank Sizes (gal): Septic Tank: 1000

Pump Chamber: 500

Grease Trap:

LTAR: .25

Trenches: Length (ft): 360

Width (in): 36

Max. Depth (in): 36

Agg. Depth (in):

Min Pump Capacity:

gpm at

ft. of head

Alternative Product: INFILTRATOR QUICK4 CHAMBER

SPECIAL INSTRUCTIONS/CONDITIONS

THIS PERMIT IS SITE SPECIFIC. ANY CHANGES TO THE SYSTEM MUST BE APPROVED BY DHEC. ALTERNATIVE TRENCH PRODUCTS APPROVED UNDER STATE RULES AND REGULATIONS MAY BE SUBSTITUTED. ANY UNAPPROVED CHANGES WILL VOID THIS PERMIT.
Installers must contact the local Environmental Affairs office by 10:00 AM on the day prior to installation in order to schedule a time for the final inspection.
If a Department representative does not arrive within 30 minutes of the scheduled time, the installer may conduct the final inspection.
When a contractor self-inspection occurs, the installer must complete the DHEC form 3978, Approval to Operate Contractor Self-Inspection.
The installer must submit DHEC form 3978 within 2 business days of the completion of the installation.

PERMIT TO CONSTRUCT SYSTEM DIAGRAM

(NTS)

System design By
Piedmont Soils and Wetlands LLC

ph: 803-426-1103

Soil Classifier: Lance Brewington
Lance.brewington@yahoo.com

see Attached supplemental diagram

Issued/Revised By:

Date:

9/23/20



APPLICATION SUPPLEMENTAL FORM

Onsite Wastewater System

File Nbr: **2020070005**

County: **Saluda**

Name: **JEFF RIKARD**

Address:

**3079 WINDMILL RD
LEESVILLE, SC 29070**

Program Code: **360**

Type Facility: **HOUSE**

System Code:

Subdivision **PALMETTO POINTE**

Site: **LONGVIEW DR LOT 42**

TM No.:

Block: Lot: **42**

LEESVILLE, SC

Water Supply: **PUBLIC**

ACTUAL INSTALLATION

(NTS)

